Notification dated the 5th February 1938.

Notice is hereby given, under Section 40 of the Mysore Forest Regulation, that the following timbers found unclaimed are now in the custody of persons noted against each. Claimants, if any, for the same, will establish their claims within one month from the date of publication of this notification, failing which the timber will be confiscated to Government. Any claims preferred after the due date will not be considered.

Kind	No.	Quantity	Name of Custodian	Remarks
		C.ft.		
Teak ..	3	15 11	Patel Ningappa *bin* Channabasappa of Chandankere, Holehonnur Hobli, Shimoga Taluk.	
Mathi ..	1	5 10		
Teak poles ..	3	8 5	Murugappa, Patel, Haranahalli, Channagiri Taluk	
,, ..	1	4 3	Patel Basappa, Annapur Village, Channagiri Taluk.	
,, ..	3	15 3	Range Officer's Compound, Channagiri.	
..	3	11 2	Nandyappa, son of Yedehalli, Mahadevappa, residing in Danavadi Village, Holehonnur Hobli, Shimoga Taluk.	
Teak ..	30	107 4	Ubrani Lodge.	
Yatthaga ..	1	21 11		
Teak pieces ..	34	6·4 C.ft.	Do	
Parodes ..	58			

M. G. VENKATA RAO,
District Forest Officer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 7th February 1938.

Notice is hereby given that sealed tenders will be received from the Licensed Plumbers at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 22nd February 1938, for the labour portion of the work for laying pipe lines for giving water supply to Shikarpur Town, Shimoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 125 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the labour portion of the work for laying pipe lines for giving water supply to Shikarpur Town, Shimoga District" in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates,

quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Estimate of the approximate quantities for labour portion of the work for laying pipe lines for giving water supply to Shikarpur Town, Shimoga District.

Sl. No.	Particulars	Unit	Quantity
	DRAW-OFF ARRANGEMENTS.		
1	Earthwork excavating and refilling the trench including watering and tamping for laying 6″ C.I. pipes	C.yd.	121
2	Excavating and removing earth at a distance for constructing jelly duct	,,	40
3	Laying and jointing 6″ C.I. flanged pipes, drilling holes in the flanges including bolts and nuts and rubber insertions, etc., complete ..	No.	4
4	Rough stone revetment new, including packing jelly	C.yd.	38
5	Filling in with rough stone jelly for the duct	,,	37
	LAYING 4″ C. I. RISING MAIN.		
1	Earthwork excavating, refilling the pipe trench including watering and tamping	C.yd.	522
2	Conveying and making lead joint to 4″ C.I. pipes fixing specials including laying with cuts wherever necessary	No.	165
3	Constructing valve cisterns as per type design	,,	4
	LAYING SUCTION PIPES.		
1	Earthwork excavating and refilling	C.yd.	77
2	Drilling holes to flanges	No.	65
3	Laying and jointing 3″ W.I. pipes including cutting and threading ..	R.ft.	135
	LAYING PIPES FOR DISTRIBUTION SYSTEM.		
1	Earthwork excavating and refilling the pipe trench including watering and tamping for laying C.I. pipes	C.yd.	767
2	Conveying and making cement jointing over dry lead wire joint to 3″ C.I. pipes and specials including laying and jointing with cut s etc., complete	No.	296
3	Constructing valve cisterns as per type designs	,,	1
4	Laying and jointing 2½″ G.I. pipes including cutting and threading and earthwork, etc., complete	R.ft.	1,100
5	Do 2″ G.I. pipes do ..	,,	150
6	Do 1½″ G.I. pipes do	,,	1,300
7	Do 1″ and ¾″ G.I. pipes do	,,	5,400
8	Constructing glandcock cistern as per type design	No.	31
9	Main bores (2½″, 2″, 1½″, 1″ and ¾″)	,,	16
10	Constructing platforms for public fountains as per type design ..	,,	27

N. KRISHNA IYENGAR,
Sanitary Engineer.

MYSORE DIVISION.

Notification dated 7th February 1938.

It is hereby notified that the 1st Class Travellers' Bungalow at Hunsur will be closed for the public on Tuesday the 22nd February 1938 on account of Dewan's tour.

B. KRISHNA RAO,
Executive Engineer.